



Vern Freymuth  
Commercial Sales Director  
RC Roofing, LLC  
865-850-8353

Porter Elementary, Clay Davis

clay.davis@blount12.org

4520 Wildwood Springs Road, Maryville, Tennessee, 37801

(865) 801-0296

- Remove existing shingles down to the deck. NOTE: If more than one layer of roofing is found there will be an additional charge of \$25/sq to cover labor & landfill fees.
  - Re-nail any loose wood. NOTE: If bad or rotten wood is discovered, it will be replaced at a price of \$90 per sheet or \$50 per board.
  - Furnish and Install ice and water shield at all walls, valleys, transitions, and chimneys.
  - Furnish and Install GAF FeltBuster synthetic roof underlayment using button cap fasteners.
  - Furnish and Install new vent pipe flashing boots.
  - Furnish and Install new step flashing on walls & chimney as needed; & counter flashing on the chimney as needed.
  - Furnish and Install GAF ProStart Starter Shingles along all gutter lines and rake edges.
  - Furnish and Install GAF Timberline HDZ Lifetime Dimensional Shingles per specifications using 1 1/4" roofing nails.
- COLOR: \_\_\_\_\_
- Cut out ridge cap & install a new ridge vent.
  - Cut out plywood about 1 foot up from eave edge to allow attic space to vent properly.
  - Furnish and Install GAF Seal-A-Ridge Hip & Ridge Shingles.
  - Furnish and Install drip edge around the perimeter of the roof.
  - Clean up all job-related debris.
  - Provide 10 yr workmanship warranty and provide the owner with GAF SYSTEM PLUS WARRANTY.
  - Our Crews are licensed and insured.
  - Crews will maintain safety requirement at all times during the construction process.

NOTE: If the roofs have a satellite dish is the homeowner's responsibility to call the satellite dish provider to install the dish again. We recommend being installed in the gable or other structure, not on the roof.

The #1 ingredient to a good roof system is PROPER INSTALLATION.

Due to the volatility of material pricing currently, this proposal is valid for 14 days. IF during that 14 days material prices increase more than 3% that increase will be passed along to the property owner.

For your convenience we offer financing. ask our sales representative for more information.

Payment made as follows: 50% down payment, remaining balance due upon completion.

added to the transaction.

**Total Price 18,940.00**

Signature Date

Signature Date



Vern Freymuth  
Commercial Sales  
RC Roofing, LLC  
865-850-8353

Union Grove Middle School, Clay Davis

clay.davis@blount12.org

334 South Old Grey Ridge Road, Friendsville, Tennessee,

(865) 801-0296

- Remove existing shingles down to the deck. NOTE: If more than one layer of roofing is found there will be an additional charge of \$25/sq to cover labor & landfill fees.
  - Re-nail any loose wood. NOTE: If bad or rotten wood is discovered, it will be replaced at a price of \$90 per sheet or \$50 per board.
  - Furnish and Install ice and water shield at all walls, valleys, transitions, and chimneys.
  - Furnish and Install GAF FeltBuster synthetic roof underlayment using button cap fasteners.
  - Furnish and Install new vent pipe flashing boots.
  - Furnish and Install new step flashing on walls & chimney as needed: & counter flashing on the chimney as needed.
  - Furnish and Install GAF ProStart Starter Shingles along all gutter lines and rake edges.
  - Furnish and Install GAF Timberline HDZ Lifetime Dimensional Shingles per specifications using 1 1/4" roofing nails.
- COLOR: \_\_\_\_\_
- Cut out ridge cap & install a new ridge vent.
  - Furnish and Install GAF Seal-A-Ridge Hip & Ridge Shingles.
  - Furnish and Install drip edge around the perimeter of the roof.
  - Clean up all job-related debris.
  - R&R old Modified roofing on small flat roof on side of concession stand.
  - Provide 10 yr workmanship warranty and provide the owner with GAF SYSTEM PLUS WARRANTY.
  - Our Crews are licensed and insured.
  - Crews will maintain safety requirement at all times during the construction process.

NOTE: If the roofs have a satellite dish is the homeowner's responsibility to call the satellite dish provider to install the dish again. We recommend being installed in the gable or other structure, not on the roof.

The #1 ingredient to a good roof system is PROPER INSTALLATION.

Due to the volatility of material pricing currently, this proposal is valid for 14 days. IF during that 14 days material prices increase more than 3% that increase will be passed along to the property owner.

For your convenience we offer financing, ask our sales representative for more information.

Payment made as follows: 50% down payment, remaining balance due upon completion

added to the transaction.

**Total price \$12,300.00**

Signature Date

Signature Date