

Plant & Office:
2535 Asbury Road
P.O. Box 53426
Knoxville, TN 37950-3426



Phone:
(865) 524-3365
Fax: (865) 524-1263

October 16, 2025

Blount County Schools

Attn: Clay Davis

Re: Parking Lot Repair for
William Blount High School
219 County Farm Road
Maryville Tn. 37801

20240094-KCP3447

Clay,

Thank you for the opportunity to quote the above referenced project. Below I have provided you top options for paving the damaged lot at William Blount high School with an add estimate for curbing repair. Duracap Asphalt proposes to furnish the necessary labor and materials required to install the following:

Repair Option #1 by Provided Specs:

Item #1---Saw cut and remove 659 Sqyds of Damaged Asphalt to a depth of 10.5" deep, haul off materials and dispose.

Item #2---Install 659 Sqyds of Heavy Duty Asphalt Paving---6" Base stone, 2.5" B-mod binder, Tack Coat and 2" E surface mix.

Item #3---Stirpe Parking lot to match existing paint scheme

For This work Duracap Asphalt Paving Co. Inc. bids **\$69,996.00**

Note: This estimate is based on the current TDOT Bituminous Index for October 2025 asphalt index and is subject to increase at the time of asphalt installation.

Repair Option #2 by Duracap Reccomendations:

Item #1---Saw cut and remove 659 Sqyds of Damaged Asphalt to a depth of 8.5" deep, haul off materials and dispose.

Item #2---Install 659 Sqyds of Heavy Duty Asphalt Paving---6" Base stone, 2.5" B-mod binder

Item #3---Clean Parking Lot by sweeping and blowing

Item #4---Install 922 Sqyds of Asphalt Surface Paving over entire lot---Tack Coat level where needed and 1.5" E surface mix.

Item #5---Stirpe Parking lot to match existing paint scheme

For This work Duracap Asphalt Paving Co. Inc. bids **\$71,455.00**

Note: This estimate is based on the current TDOT Bituminous Index for October 2025 asphalt index and is subject to increase at the time of asphalt installation.

Add for Curbing Repair if required:

Item #1---Install 125 Lft of new concrete curbing on site

For this work **Please add \$6,997.00** to one of the above bids

NOTES:

1. Grade contractor to grade sub-grade elevations to within $\pm 1/10^{\text{th}}$ foot of finished sub-grade.
2. This proposal may be withdrawn by us if not accepted within 14 days. Work to be completed during the current paving season unless otherwise mutually agreed upon.
3. This proposal is subject to credit approval, approved scheduling of work, and timely execution of contract documents.
4. All projects are bid to be completed in one mobilization. Any additional mobilizations will result in additional charges.
5. Payment in full is due by 10th following.
6. Material thickness is an average thickness unless otherwise specified and may vary in areas to achieve required or needed drainage.
7. Proposal does not include any fees, permits, or material testing.
8. All lot lines, center lines, and engineering layout furnished by owner.
9. Prime Coat is not included unless it is expressed in "item paving description" or is listed as a separate item.
10. Unless listed in "item paving description", we do not include any above ground signage.
11. In the event the services of an attorney are needed for collection of any amount due or payable under this contract, either for suite or otherwise, you shall be liable for all cost and expenses incurred for or in connection with such collection or suit, including without limitation, reasonable attorney's fees.
12. Our work is guaranteed for one year against defects in workmanship and quality of materials.
13. Duracap Asphalt Paving Co. Inc. will not warranty any work with less than 1% drainage.

Submitted by:

Brian D. Smith

Brian D. Smith

Estimator

Acceptance – The above prices, specifications, and conditions are satisfactory and are hereby accepted. You are authorized to do the work specified. Payment will be made as outlined above.

Date of Acceptance _____ Signature _____

Printed Name & Title _____