


# RIDGEVIEW BAPTIST CHURCH 3409 TUCKALEECHEE PIKE MARYVILLE, TENNESSEE 37803







IF THIS DOCUMENT IS NOT SIGNED, SEALED, AND DATED, IT MAY NOT BE USED FOR CONSTRUCTION

## **DRAWING INDEX**

**COVER SHEET GENERAL NOTES** 

**EXISTING CONDITIONS AND DEMOLITION PLAN** 

SITE LAYOUT PLAN

SIGHT DISTANCE EXHIBITS SIGHT DISTANCE EXHIBITS

SITE GRADING & DRAINAGE PLAN INITIAL EROSION CONTROL PLAN

FINAL EROSION CONTROL PLAN

SITE DETAILS

**UTILITIES PLAN** 

Titute the state of the state o
The state of the s
LOCATION MAP

PROPERTY DATA			
PROPERTY OWNER	RIDGEVIEW BAPTIST CHURCH 4234 GAMBLE LANE WALLAND, TN 37886		
CONTROL. MAP NO.	059		
PARCEL NUMBER	110.03		
JURISDICTION	BLOUNT COUNTY, TN		
ZONING	S-SUBURBANIZING		
AREA	306,227 S.F. / 7.03 AC.		



RIDGEVIEV

865.670.8555 www.cci-corp.com

RIDGEVIEW BAPTIST CHURCH 4234 GAMBLE LANE WALLAND, TN 37886 PASTOR WAYNE SEXTON

CCI PROJ. NO.	01851-0000.000
DATE:	JULY 23, 2025
PM/PC:	BCW
DRAWN BY:	RHE

**COVER SHEET** 

C001

- 1. OWNERSHIP AND REFERENCE PARCEL ID 059 110.03 3409 TUCKALEECHEE PIKE MARYVILLE. TN 37903
- CLT MAP 59, PARCEL 110.03 2. TOTAL SITE AREA: 306,227 S.F. / 7.03 AC.
- 3. TOTAL DISTURBED AREA: 136,571 S.F. / 3.14 AC. 4. THE BOUNDARY DATA SHOWN WAS PROVIDED BY STERLING ENGINEERING, INC., DATED APRIL 25, 2023. THE TOPOGRAPHIC DATA SHOWN WAS PROVIDED BY STERLING ENGINEERING, INC. DATED APRIL 25, 2023.
- 5. ABOVE GROUND AND UNDERGROUND UTILITIES AS SHOWN WERE LOCATED FROM VISIBLE FIELD EVIDENCE, UTILITY MARKINGS AND/OR DRAWINGS BY OTHERS. VERIFICATION AS TO EXISTENCE, LOCATION, SIZE, MATERIAL AND DEPTH SHOULD BE PURSUED PRIOR TO ANY DECISIONS BEING MADE RELATIVE TO UTILITIES. TO AVOID CONFLICTS AND/OR HAZARDS, NOTIFY TENNESSEE ONE CALL PRIOR TO ANY EXCAVATION OR GRADING ACTIVITIES.
- PROPERTY CONCERNED REFLECTS PARCEL 110.03 AS SHOWN ON BLOUNT COUNTY CLT TAX MAP NO. 59.
- PROPERTY ZONED: S (SUBURBANIZING) 8. ALL SETBACKS SHALL BE IN ACCORDANCE WITH THE BLOUNT COUNTY ZONING ORDINANCE. THE MINIMUM SETBACKS FOR MAIN STRUCTURES WILL BE AS FOLLOWS:

FRONT: THIRTY (30) FEET. TEN (10) FEET. SIDE:

TWENTY (20) FEET PRINCIPLE, FIVE (5) ACCESSORY STRUCTURE

- SUBJECT PROPERTY LIES OUTSIDE THE 100 YEAR FLOODWAY PER FIRM MAPPING OF BLOUNT COUNTY, TENNESSEE. COMMUNITY PANEL NO: 47009C0144C DATED 9/19/2007.
- 10. DEVELOPER: RIDGEVIEW BAPTIST CHURCH 4234 GAMBLE DRIVE WALLAND, TN 37886

#### SITE DEMOLITION NOTES

- CONTRACTOR SHALL OBTAIN ALL PERMITS AND APPROVALS REQUIRED TO PERFORM DEMOLITION WORK.
- INSTALL EPSC MEASURES PRIOR TO SITE DEMOLITION. CONTRACTOR TO COORDINATE WITH APPROPRIATE UTILITY PRIOR TO DEMOLITION OF EXISTING SITE UTILITIES. TERMINATION OF UTILITIES SHALL BE IN ACCORDANCE WITH THE UTILITY REQUIREMENTS. CONTRACTOR IS SOLELY RESPONSIBLE FOR VERIFYING FIELD CONDITIONS WITH THE APPROPRIATE UTILITY. CONFIRM IF REMOVAL WILL AFFECT ANY OTHER UTILITY SERVICES IN OPERATION. IF IT IS DETERMINED THE UTILITY LINE NEEDS TO REMAIN IN SERVICE,
- COORDINATE RELOCATION/REPLACEMENT WITH OWNER. 4. ALL ABANDONED UTILITY LINES AND APPURTENANCES SHALL
- BE REMOVED & DISPOSED OF PROPERLY. 5. CONTRACTOR TO ENSURE ALL EXISTING CUSTOMERS IN PROJECT AREA HAVE RELOCATED AND THAT ALL TERMINATION OF SERVICES HAVE BEEN APPROVED BY THE UTILITY PROVIDERS PRIOR TO DEMOLITION.
- 6. CONTRACTOR SHALL PROPERLY DISPOSE OF DEMOLITION MATERIAL OFFSITE.
- CONTRACTOR TO PERFORM DEMOLITION OF RETAINING WALLS. BUILDING WALLS, FOUNDATIONS, PAVEMENT, UNDERGROUND UTILITIES. ETC. AS REQUIRED TO INSTALL THE PROPOSEL PLAN AS SHOWN.
- 8. EXCAVATIONS FROM DEMOLITION ARE TO BE BACKFILLED WITH SOIL OR ENGINEERED FILL IN ACCORDANCE WITH RECOMMENDATIONS BY A GEOTECHNICAL ENGINEER. CONTRACTOR SHALL PROVIDE A PLAN AS NEEDED FOR DEWATERING OF EXCAVATION AREAS.
- 9. THE UTILITY SERVICES SHOWN ARE BASED ON THE AVAILABLE INFORMATION PROVIDED. ADDITIONAL SERVICE LINES WHICH ARE NOT SHOWN MAY BE ENCOUNTERED DURING DEMOLITION. ALL UTILITY SERVICES CONNECTING TO THE BUILDING WILL BE REMOVED FROM WITHIN THE LIMITS OF DEMOLITION UNLESS OTHERWISE NOTED ON THE DEMOLITION PLANS. ALL SERVICES SHALL BE TERMINATED OR CAPPED IN ACCORDANCE WITH UTILITY PROVIDER GUIDELINES.

#### **GENERAL SITE NOTES**

- 1. PRIOR TO BEGINNING ANY CONSTRUCTION. THE DEVELOPER AND/OR CONTRACTOR, SHALL OBTAIN ALL NECESSARY PERMITS AS REQUIRED BY LAW OR THE GOVERNING JURISDICTIONS. SUCH PERMITS MAY INCLUDE, BUT ARE NOT LIMITED TO. THOSE REQUIRED BY STATE OF TENNESSEE AND BLOUNT COUNTY. 2. UNLESS NOTED OTHERWISE. DIMENSIONS ARE TAKEN FROM
- OUTSIDE FACE OF BUILDING AND/OR FACE OF CURB. 3. THE MINERAL AGGREGATE BASE AND ASPHALTIC SURFACE COURSES SHALL MEET THE MATERIALS, EQUIPMENT, CONSTRUCTION, AND TESTING REQUIREMENTS OF THESE
- DRAWINGS, THE TENNESSEE DEPARTMENT OF TRANSPORTATION (TDOT), AND BLOUNT COUNTY STANDARD SPECIFICATIONS.
- TRAFFIC CONTROL DEVICES AND PAVEMENT MARKING SHALL CONFORM TO THE FEDERAL HIGHWAY ADMINISTRATION "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES."
- ALL OFF-SITE WORK WITHIN THE PUBLIC RIGHT-OF-WAY SHALL REQUIRE AN APPROVED TRAFFIC CONTROL PLAN WHICH COMPLIES WITH THE MUTCD. THE CONTRACTOR SHALL HAVE AN APPROVED TRAFFIC CONTROL PLAN ONSITE DURING CONSTRUCTION.
- CONTRACTOR IS RESPONSIBLE FOR REPAIRING RIGHT-OF-WAY ELEMENTS DAMAGED DURING CONSTRUCTION PER BLOUNT COUNTY STANDARDS.
- LOCATING AND COORDINATION FOR THE RELOCATION OF EXISTING UTILITIES IS THE RESPONSIBILITY OF THE CONTRACTOR. TENNESSEE'S ONE-CALL SHALL BE UTILIZED IN ADDITION TO COORDINATION WITH LOCAL UTILITY OWNERS. THE CONTRACTOR SHALL AT ALL TIMES PROTECT EXISTING UTILITIES AND WILL BE RESPONSIBLE FOR COSTS DUE TO DAMAGE CAUSED TO ANY UTILITY LINES.

#### STORM PIPE NOTES

- . INSTALL STORM SEWER PIPING AND APPURTENANCES TO MEET THE MATERIALS, EQUIPMENT, AND CONSTRUCTION REQUIREMENTS OF TDOT AND BLOUNT COUNTY STANDARD SPECIFICATIONS.
- 2. TRENCH DESIGN AND SAFETY FOR PIPELINE CONSTRUCTION IS SOLELY THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL CONFORM WITH ALL APPLICABLE LOCAL, STATE, AND
- OSHA REGULATIONS. 3. STORM SEWER PIPE SHALL BE REINFORCED CONCRETE PIPE IN ACCORDANCE WITH AASHTO M170 OR EQUAL, OR SMOOTH INTERIOR HIGH DENSITY POLYETHYLENE PIPE IN ACCORDANCE WITH AASHTO M294 OR EQUAL. REFER TO THE STORM PIPE TABLES FOR PIPE MATERIAL, SIZE, AND SLOPE.
- 4. PIPE DEFLECTION AND ALIGNMENT SHALL BE CHECKED AFTER BACKFILLING & COMPACTION ARE COMPLETE & PRIOR TO PLACING THE BASE. TEST DEFLECTION WITH A MANDREL OR OTHER APPROVED METHOD.
- 5. PIPE WITH DEFLECTION 5% OR GREATER OR WITH UNDUE MISALIGNMENT SHALL BE REPLACED AT THE CONTRACTOR'S 6. STORM PIPE LENGTHS LOCATED IN STORM PIPE TABLE
- REPRESENT CENTER OF STRUCTURE TO CENTER OF STRUCTURE (COORDINATE TO COORDINATE). CONTRACTOR TO ADJUST LENGTHS AS NEEDED BASED ON SIZE OF STRUCTURE (REFER TO STORM DATA TABLES).
- 7. ROOF DRAINS AND DOWNSPOUT LEADERS SHALL BE SDR 35 PVC OR SMOOTH INTERIOR HDPE. SLOPE 4" LEADERS AT A MINIMUM 2% SLOPE AND 6" OR LARGER LEADERS AT A MINIMUM 1% SLOPE. CLEANOUTS LOCATED IN TRAFFIC AREAS TO BE HEAVY DUTY RATED. REFER TO DOWNSPOUT/ROOF DRAIN CONNECTION DETAILS FOR ADDITIONAL INFORMATION. DOWNSPOUT LOCATIONS TO BE COORDINATED WITH ARCHITECTURAL DRAWINGS.

#### GENERAL GRADING NOTES

- 1. UNLESS NOTED OTHERWISE, THE PROPOSED GRADES SHOWN ON THESE DRAWINGS ARE FINISHED GRADE. CONTRACTOR TO ADJUST FOR PAVEMENT, TOPSOIL, ETC. THICKNESS AS REQUIRED. EXISTING AND PROPOSED CONTOURS ARE SHOWN AT 1 FT. INTERVALS.
- 2. EROSION CONTROL DEVICES SHALL BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE TENNESSEE EROSION AND SEDIMENT CONTROL HANDBOOK. THE DEVICES SHOWN ON THE DRAWINGS ARE THE MINIMUM REQUIRED. THE CONTRACTOR SHALL PROVIDE ADDITIONAL EROSION CONTROL DEVICES AS NEEDED.
- 3. THE SITE SHALL BE CLEARED AND GRUBBED WITHIN THE LIMITS OF EXCAVATION. COMPLETELY DISPOSE OF ALL MATERIALS RESULTING FROM CLEARING AND GRUBBING OFF-SITE OR ON-SITE AT A LOCATION DETERMINED BY THE
- 4. ALL TREE STUMPS, BOULDERS, AND OTHER OBSTRUCTIONS SHALL BE REMOVED TO A DEPTH OF 2 FT BELOW THE SUBGRADE. ROCK SHALL BE SCARIFIED TO A DEPTH OF 1 FT BELOW SUBGRADE.
- 5. STRIP TOPSOIL TO A DEPTH AS REQUIRED BY GEOTECHNICAL ENGINEER. STRIP TOPSOIL ONLY FROM AREAS THAT WILL BE DISTURBED BY EXCAVATION, FILLING, PAVING, OR COMPACTION BY EQUIPMENT. TEMPORARILY STOCKPILE EXCAVATED MATERIALS AND INSTALL SILT FENCE OR OTHER APPROPRIATE EROSION CONTROL STRUCTURES ON THE DOWN HILL SIDE OF THE STOCKPILE.
- 6. PROOF ROLL AREAS TO RECEIVE FILL AND PLACE FILL IN ACCORDANCE WITH THE SITE SPECIFIC REPORT OF GEOTECHNICAL EXPLORATION PREPARED BY UES PROFESSIONAL SOLUTIONS 19, LLC DATED MARCH 5, 2025.
- 7. A 4 IN. MINIMUM UNIFORM LAYER (SETTLED) OF TOPSOIL SHALL BE PLACED OVER THE AREAS TO BE SEEDED AND TO THE FINISHED GRADE ELEVATIONS AS SHOWN ON THE DRAWINGS.
- 8. ALL NEWLY GRADED EARTHEN AREAS THAT ARE NOT TO BE PAVED, STABILIZED, OR SODDED SHALL BE SEEDED, FERTILIZED, AND MULCHED WITHIN 30 DAYS OF ATTAINMENT OF FINAL GRADE. REFER TO SEEDING MIXTURE CHART ON
- THIS SHEET FOR ADDITIONAL INFORMATION. 9. MULCH WITH STRAW AT A RATE OF 100 LBS/1000 SF OVER THE SEEDED AREAS.
- 10. DO NOT ALLOW WATER TO ACCUMULATE IN EXCAVATIONS OR POND ON-SITE. PROVIDE NECESSARY MEASURES TO KEEP THE SITE FREE-DRAINING.
- 11. PERIMETER SLOPES SHALL BE LANDSCAPED AND ARE NOT TO EXCEED 2:1 (H: V) UNLESS PROPER STABILIZATION IS PROPOSED BY A GEOTECHNICAL ENGINEER. NO SLOPE SHALL EXCEED 2:1 (H: V). ALL SLOPES STEEPER THAN 3:1 TO RECEIVE EROSION CONTROL BLANKET.
- 12. TO PREVENT EROSION, ALL SLOPES 2:1 OR GREATER ARE TO BE TRACKED WITH A DOZER TO FORM CLEAT MARKS PARALLEL TO THE CONTOUR.
- 13. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS POSSIBLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED.
- 14. APPLY TEMPORARY SEEDING WHENEVER GRADING OPERATIONS ARE HALTED FOR OVER 14 DAYS. APPLY TEMPORARY SEEDING TO ALL SOIL STOCKPILES. STEEP SLOPES (SLOPES GREATER THAN 35%) SHALL BE STABILIZED WITHIN 7 DAYS AFTER CONSTRUCTION ACTIVITY ON THE
- SLOPE HAS TEMPORARILY OR PERMANENTLY CEASED. 15. APPLY PERMANENT SEEDING WHENEVER GRADING OPERATIONS ARE COMPLETED AND ALL CONSTRUCTION OPERATIONS WILL NOT IMPACT THE DISTURBED AREA. APPLY PERMANENT SEEDING TO ALL NON-CONSTRUCTION AREAS WHICH SHOW SIGNS OF EXCESSIVE EROSION.

TEMP. INLET PROTECTION

TEMP. ROCK CHECK DAM

TEMP. ENHANCED CHECK DAM

EROSION CONTROL BLANKET

STONE FILTER RING

#### **GENERAL EROSION CONTROL NOTES**

- 1. INITIAL EROSION CONTROL MEASURES AS SHOWN ON THE EROSION CONTROL SHEETS SHALL BE INSTALLED AS FIRST ITEM OF CONSTRUCTION. THESE ITEMS SHALL BE COMPLETED PRIOR TO COMMENCING WITH SITE CLEARING, GRUBBING, AND GRADING OPERATIONS.
- 2. PRE-CONSTRUCTION VEGETATIVE GROUND COVER SHALL NOT BE DESTROYED. REMOVED. OR DISTURBED MORE THAN 15 DAYS PRIOR TO GRADING OR EARTH MOVING UNLESS THE AREA IS SEEDED AND/OR MULCHED OR OTHER TEMPORARY COVER IS INSTALLED.
- 3. EXISTING VEGETATION SHOULD BE PRESERVED TO THE MAXIMUM EXTENT PRACTICABLE.
- 4. SEDIMENT MUST BE REMOVED FROM SEDIMENT TRAPS, SILT FENCES, AND OTHER SEDIMENT CONTROLS WHEN DESIGN CAPACITY HAS BEEN REDUCED BY 50%. SEDIMENT SHALL BE REMOVED FROM SEDIMENT BASINS WHEN IT REACHES 1/4 TO 1/3 OF THE TOTAL STORAGE VOLUME.
- 5. ADEQUATE DRAINAGE, EROSION AND SEDIMENT CONTROL MEASURES, BEST MANAGEMENT PRACTICES AND/OR OTHER STORMWATER MANAGEMENT FACILITIES SHALL BE PROVIDED AND MAINTAINED AT ALL TIMES DURING CONSTRUCTION. DAMAGES TO ADJACENT PROPERTY AND/OR THE CONSTRUCTION SITE CAUSED BY THE CONTRACTOR'S OR PROPERTY OWNER'S FAILURE TO PROVIDE AND MAINTAIN ADEQUATE DRAINAGE AND EROSION/SEDIMENT CONTROL FOR THE CONSTRUCTION AREA SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND/OR PROPERTY OWNER.
- 6. QUALITY ASSURANCE OF EROSION PREVENTION AND SEDIMENT CONTROLS SHALL BE CONDUCTED BY QUALIFIED PERSONNEL PERFORMING SITE ASSESSMENT AT EACH OUTFALL INVOLVING DRAINAGE TOTALING 10 OR MORE ACRES, OR FIVE OR MORE ACRES IF DRAINING TO IMPAIRED OR EXCEPTIONAL WATERS. THIS ASSESSMENT WILL BE CONDUCTED AT EACH QUALIFYING OUTFALL WITHIN A MONTH OF CONSTRUCTION COMMENCEMENT IN ACCORDANCE WITH THE LATEST CONSTRUCTION GENERAL PERMIT.
- 7. FUGITIVE SEDIMENT THAT HAS ESCAPED THE CONSTRUCTION SITE MUST BE REMOVED SO THAT IT IS NOT SUBSEQUENTLY WASHED INTO STORM SEWERS AND/OR STREAMS BY THE NEXT RAIN AND/OR SO THAT IT DOES NOT POSE A SAFETY HAZARD TO USERS OF PUBLIC STREETS. ARRANGEMENTS CONCERNING REMOVAL OF SEDIMENT ON ADJOINING PROPERTY MUST BE SETTLED BY THE PERMITTEE WITH THE ADJOINING LAND OWNER.
- LITTER, CONSTRUCTION DEBRIS, AND CONSTRUCTION CHEMICALS EXPOSED TO STORMWATER SHALL BE PICKED UP PRIOR TO ANTICIPATED STORM EVENTS OR BEFORE BEING CARRIED OFF THE SITE BY WIND, OR OTHERWISE PREVENTED FROM BECOMING A POLLUTION SOURCE FOR STORMWATER DISCHARGES.
- 9. INSPECTIONS OF OUTFALLS/EPSC MEASURES SHALL BE CONDUCTED AT LEAST TWICE WEEKLY AND AT LEAST 72 HOURS APART OR AS REQUIRED IN THE LATEST CONSTRUCTION GENERAL PERMIT.
- 10. VEGETATION, EPSCs & OTHER PROTECTIVE MEASURES SHALL BE REPAIRED, REPLACED, OR MODIFIED WITHIN 7 DAYS OF BEING NOTIFIED OF AN ISSUE.
- 11. CONSTRUCTION SHALL BE PHASED FOR ACTIVITIES THAT WILL DISTURB > 50 ACRES.
- 12. EPSCs SHALL BE DESIGNED TO CONTROL THE RAINFALL AND RUNOFF FROM A 2-YR, 24-HOUR RETURN INTERVAL STORM 13. TEMPORARY SEDIMENT BASIN(S) SHALL BE PROVIDED FOR ON-SITE OUTFALLS THAT RECEIVE DRAINAGE FROM > 10 ACRES: > 5 ACRES FOR SITES THAT DISCHARGE TO WATERS WITH UNAVAILABLE PARAMETERS FOR SILTATION OR EXCEPTIONAL TN WATERS.
- 14. TEMPORARY SEDIMENT TRAP(S) SHALL BE PROVIDED FOR ON-SITE OUTFALLS THAT RECEIVE DRAINAGE FROM > 3.5 ACRES FOR SITES THAT DISCHARGE TO WATERS WITH UNAVAILABLE PARAMETERS FOR SILTATION OR EXCEPTIONAL TN WATERS.
- 15. GREEN INFRASTRUCTURE BMPs (INFILTRATION AREAS) SHALL BE PROTECTED DURING SITE WORK, WITH SILT FENCE OR ADDITIONAL EROSION CONTROL MEASURES AS REQUIRED TO PREVENT SEDIMENTATION AND COMPACTION.
- 16. TEMPORARY SEDIMENT BASINS OR TRAPS SHALL REMAIN IN PLACE UNTIL SITE IS STABILIZED AND ALL FUTURE SECTIONS ARE COMPLETE. SEDIMENT BASINS USED AS PERMANENT DETENTION PONDS SHALL BE CONVERTED TO DETENTION STRUCTURES AFTER FINAL STABILIZATION OF SITE.
- 17. TDEC TRACKING NUMBER FOR THIS PROPERTY IS TNR137961 18. IF OFF-SITE BORROW MATERIAL IS UTILIZED, A COPY OF PERMIT SHALL BE PROVIDED TO BLOUNT COUNTY.

#### **GENERAL SITE UTILITY NOTES**

- 1. THE LOCATIONS OF THE EXISTING UTILITIES SHOWN ON THESE DRAWINGS ARE APPROXIMATE. THE EXACT LOCATIONS SHALL BE DETERMINED IN THE FIELD BY CONTACTING THE APPROPRIATE UTILITY COMPANIES INVOLVED.
- 2. PROVIDE ALL NECESSARY PROTECTIVE MEASURES TO SAFEGUARD THE EXISTING UTILITIES FROM DAMAGE DURING THE CONSTRUCTION OF THIS PROJECT. FURNISH ANY SPECIAL EQUIPMENT REQUIRED TO WORK OVER AND AROUND THE UTILITIES.
- 3. TRENCHING FOR UTILITIES IN PAVED AREAS SHALL BE REPAIRED TO MEET STANDARDS APPLICABLE TO THE GOVERNING AGENCY.
- 4. CONTRACTOR TO INSTALL ALL WATER LINES AND
- APPURTENANCES PER MANUFACTURER'S SPECIFICATIONS. 5. TRENCH DESIGN AND SAFETY FOR PIPELINE CONSTRUCTION IS SOLELY THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL CONFORM WITH ALL APPLICABLE LOCAL, STATE, AND OSHA REGULATIONS.
- 6. THE STONE BEDDING AND BACKFILL SHALL BE INSTALLED IN STRICT COMPLIANCE WITH THE PIPE MANUFACTURER'S RECOMMENDATIONS AND/OR THE APPLICABLE UTILITY PROVIDER.
- 7. WATER LINE PIPE SHALL BE IN ACCORDANCE WITH BLOUNT COUNTY BUILDING CODE REQUIREMENTS; FROM THE METER TO THE MAIN SYSTEM SHALL MEET SOUTH BLOUNT UTILITY DISTRICT REQUIREMENTS.
- 8. WATER SERVICE PIPE LARGER THAN 2 INCH IN DIAMETER SHALL BE DUCTILE IRON (CLASS 350) OR SHALL BE HDPE 3408 WITH BLUE STRIPES OR BLUESHELL MANUFACTURED IN ACCORDANCE WITH AWWA C906 AND NSF 61. SERVICE PIPE 2 INCH IN DIAMETER AND SMALLER SHALL BE TYPE-K COPPER MEETING ASTM B88 OR SHALL BE HDPE 3408 WITH BLUE STRIPES OR BLUESHELL MANUFACTURED IN ACCORDANCE WITH AWWA C901 AND NSF 61. PIPES LARGER THAN 2 INCH SHALL BE DUCTILE IRON PIPE SIZE (DIPS) IN COMPLIANCE WITH AWWA C906 AND ASTM F 714. PIPES 2 INCH AND LESS SHALL BE IRON PIPE SIZE (IPS) IN COMPLIANCE WITH AWWA C901 AND ASTM D3035. HDPE PIPE 2 INCH AND LARGER SHALL BE SDR 11 AND PIPE SMALLER THAN 2 INCHES SHALL BE SDR 9.
- 9. ALL WATER LINE MATERIAL SHALL BE LEAD FREE. 10. CONTRACTOR TO INSTALL WATER LINES AT A POSITIVE GRADE BETWEEN DESIGNATED HIGH AND LOW POINTS TO PREVENT TRAPPING OF AIR. AIR RELEASE VALVES SHALL BE INSTALLED AT HIGH POINTS IN THE PROPOSED WATER LINE.
- 11. CONTRACTOR TO USE FITTINGS WITH REACTION BLOCKING AS REQUIRED FOR PROPER HORIZONTAL AND VERTICAL ALIGNMENT. 12. ALL SANITARY SEWER LINES AND APPURTENANCES SHALL BE
- INSTALLED IN ACCORDANCE WITH BLOUNT COUNTY BUILDING CODE REQUIREMENTS; FROM MAIN TO PRIVATE SEWER CLEANOUT SHALL MEET SOUTH BLOUNT UTILITY DISTRICT REQUIREMENTS. 13. SANITARY SEWER LATERALS SHALL BE SDR 26 PVC FOR PIPE

FROM 4 INCHES TO 15 INCHES IN DIAMETER UNLESS NOTED

- OTHERWISE. PIPE SHALL MEET THE REQUIREMENTS OF ASTM 14. REFERENCE BUILDING PLUMBING, ELECTRIC, AND MECHANICAL DRAWINGS FOR LOCATION OF UTILITY CONNECTIONS. INCLUDE FITTINGS AS REQUIRED TO MATCH BUILDING SERVICE SIZES
- AND MATERIALS. 15. ALL INTERIOR FLOOR DRAINS WILL BE CONNECTED TO THE SANITARY SYSTEM.
- 16. THE WATER SYSTEMS FOR EACH BUILDING WILL NOT BE TIED TOGETHER.
- 17. IRRIGATION SERVICES SHALL INCLUDE BACKFLOW PREVENTION AS REQUIRED BY SOUTH BLOUNT UTILITY DISTRICT.

### **UTILITY SERVICE PROVIDERS**


SOUTH BLOUNT UTILITY DISTRICT 320 PARTNERSHIP PKWY MARYVILLE, TN 37801 (865) 982-3560


ELECTRIC CITY OF ALCOA 223 ASSOCIATES BLVD. ALCOA, TN 37701 (865) 380-4700

#### SEEDING MIXTURE CHART:

1. TEMPORARY SEEDING MIXTURES SHALL BE AS FOLLOWS: SEEDING DATES | GRASS SEED | PERCENTAGES ITALIAN RYE *33%* KOREAN LESPEDEZA SUMMER OATS 34% SUDAN - SORGHUM 100% STAR MILLET 100% BALBOA RYE ITALIAN RYF

	ITALIAN KIE	33%
2. PERMANENT SEED	ING MIXTURES SHALL BE AS	FOLLOWS:
SEEDING DATES	GRASS SEED	PERCENTA
2/1 TO 7/1	KENTUCKY 31 FESCUE	80%
	KOREAN LESPEDEZA	15%
	ENGLISH RYE	<i>5%</i>
6/1 TO 8/15	KENTUCKY 31 FESCUE	<i>55%</i>
	ENGLISH RYE	20%
	KOREAN LESPEDEZA	15%
	GERMAN MILLET	10%
4/15 TO 8/15	BERMUDAGRASS (HULLED)	70%
	ANNUAL LESPEDEZA	30%
8/1 TO 12/1	KENTUCKY 31 FESCUE	70%
	ENGLISH RYE	20%
	WHITE CLOVER	10%
2/1 TO 12/1	KENTUCKY 31 FESCUE	70%
	CROWN VETCH	<i>25%</i>
	ENGLISH RYE	<i>5%</i>





PATED, IT MAY NOT BE USED FOR CONSTRUCTION

S

**~** 



Knoxville, TN 37932

865.670.8555 www.cci-corp.com

CLIENT:

RIDGEVIEW BAPTIST CHURCH 4234 GAMBLE LANE WALLAND, TN 37886 PASTOR WAYNE SEXTON

CCI PROJ. NO.	01851-0000.000	
DATE:	JULY 23, 2025	
PM/PC:	BCW	
DRAWN BY:	RHE	

**GENERAL NOTES** 

**C002** 

LEGEND

ASPHALT PVMT (LIGHT DUTY) ASPHALT PVMT (HEAVY DUTY) CONCRETE SIDEWALK

—— — EXIST. R.O.W./PROPERTY LINE \_ \_ \_ \_ \_ \_ BUILDING SETBACK LINE ---- EASEMENT LINE (DETAIL NO.)

(SHEET NO.)

CONCRETE PAVEMENT

C401/

NUMBER OF PARKING SPACES COORDINATE POINT

ACCESSIBLE PARKING SYMBOL ACCESSIBLE CURB RAMP

EXISTING CONTOUR ------890------ PROPOSED CONTOUR PROPOSED SPOT ELEVATIONS: FINISH FLOOR FLEV (TC) TOP BACK CURB (BC) BOTTOM OF CURB (SW) SIDEWALK (TOS) TOP OF STEP

(BOW) BOTTOM OF WALL <u>(STORM STRUCTURE NO.)</u> (STORM STRUCTURE TYPE) ---- PROPOSED STORM CLEANOUT ----- PROPOSED UNDERDRAIN

(BOS) BOTTOM OF STEP

(TOW) TOP OF WALL

PROPOSED STORM PIPE

PROPOSED STORM STRUCTURE DRAINAGE FLOW PATH

PROPOSED DIVERSION BERM

SFB——— TEMP. SILT FENCE WITH BACKING TUBE TEMP. SEDIMENT TUBE EEL TEMP. EROSION EEL \_\_\_\_\_\_100YR**\_\_\_\_\_\_ 100-YR FL00DPLAIN** \_\_\_\_\_500YR**\_\_\_\_\_** 500-YR FLOODPLAIN ——NF—— NO-FILL LINE ZONE A—— FEMA ZONE A **——**50'BUFFER**——** SINKHOLE BUFFER

■■■■■ DRAINAGE AREA

-----SF------- TEMP. SILT FENCE

CD

———UGT——— EXISTING UNDERGROUND TELEPHONE EXISTING OVERHEAD UTILITIES \_\_\_\_OH\_\_\_\_ EXISTING FENCE \_\_\_\_X EXISTING SIGN \_\_\_ EXISTING TREE SURVEY CONTROL POINT EXISTING CATCH BASIN CORRUGATED METAL PIPE CMP REINFORCED CONCRETE PIPE EXISTING LIGHT POLE EXISTING POWER POLE EXISTING GUY ANCHOR

====ST==== EXISTING STORM SEWER PIPE

-----SA---- EXISTING SANITARY SEWER LINE

-----EXISTING LOW PRESSURE SEWER LINE

-----UGP------ EXISTING UNDERGROUND POWER LINE

— W— EXISTING WATER LINE

-----G------ EXISTING GAS LINE

EXISTING SMALL ROUND DRAIN EXISTING WATER VALVE EXISTING FIRE HYDRANT

EXISTING WATER MANHOLE EXISTING POWER MANHOLE EXISTING TELEPHONE MANHOLE **→◆♦** FH

EXISTING MAILBOX EXISTING TELEPHONE MARKER, EXISTING TELEPHONE RISER PROPOSED AIR RELEASE VALVE PROPOSED FIRE HYDRANT PROPOSED WATER BLOW-OFF VALVE PROPOSED FIRE DEPART. CONNECTION PROPOSED POST INDICATOR VALVE PROPOSED WATER VALVE PROPOSED FLUSH CONNECTION — PROPOSED E/ONE GRINDER PUMP

EXISTING GAS METER

EXISTING GAS VALVE

EXISTING GAS MARKER

EXISTING WATER METER

EXISTING SANITARY MANHOLE

PROPOSED SANITARY SEWER MANHOLE


PROPOSED WATER LINE PROPOSED WATER METER — PROPOSED GAS LINE ———LPS——— PROPOSED LOW PRESSURE SEWER PROPOSED STORM SEWER SYSTEM


PROPOSED ELECTRIC LINE


-----OHE ------ OVERHEAD ELECTRIC LINE


-----SA------ PROPOSED SEWER LINE


PROPOSED SANITARY SEWER CLEAN OUT














RIDGEVIEV
3409
MA



10025 Investment Drive, Suite 120 Knoxville, TN 37932

865.670.8555 www.cci-corp.com

CLIENT:


RIDGEVIEW BAPTIST CHURCH 4234 GAMBLE LANE WALLAND, TN 37886 PASTOR WAYNE SEXTON


01851-0000.000
JULY 15, 2025
BCW
RHE


SIGHT DISTANCE EXHIBITS

C102











SIGHT DISTANCE EXHIBITS

C103

CHARLES

CHARLES

RED ENG

AGRICULTURE

ON OOI 116

OF TEN

OF

RIDGEVIEW BAPTIST CHURCH
3409 TUCKALEECHEE PIKE
MARYVILLE, TN 37903

CANNO

10025 Investment Drive, Suite 120 Knoxville, TN 37932

865.670.8555 www.cci-corp.com

CLIENT:

RIDGEVIEW BAPTIST CHURCH


4234 GAMBLE LANE WALLAND, TN 37886 PASTOR WAYNE SEXTON

 CCI PROJ. NO.
 01851-0000.000

 DATE:
 JULY 15, 2025


 PM/PC:
 BCW

 DRAWN BY:
 RHE




	STORM DRAINAGE STRUCTURES					
NO.	DESCRIPTION	LOCATION	TOP OF CASTING	INVERT EL. (IN)	INVERT EL. (OUT)	DEPTH
1 HW	PRECAST CONCRETE HEADWALL SEE DETAIL #11, SHEET C401	N 523567.33 E 2594497.71		954.20(2)		???'
2 CB	CATCH BASIN SEE DETAIL #10, SHEET C401	N 523529.71 E 2594557.21	961.60	955.00(3)	954.90	6.70'
3 AD	AREA DRAIN SEE DETAIL #9, SHEET C401	N 523526.36 E 2594775.92	963.00	957.35(4)	957.25	5.75'
4 AD	AREA DRAIN SEE DETAIL #9, SHEET C401	N 523647.95 E 2594846.15	963.00		959.00	4.00'
5 HW	PRECAST CONCRETE HEADWALL SEE DETAIL #11, SHEET C401	N 523730.33 E 2595046.52		955.50(6)		
6 AD	AREA DRAIN SEE DETAIL #9, SHEET C401	N 523657.86 E 2594984.17	960.00		956.00	4.00'

	STORM PIPE TABLE			
FROM	то	DIAMETER	LENGTH (LF)	SLOPE (%)
2	1	15"HDPE	70	0.99%
3	2	15"HDPE	219	1.03%
4	3	15"HDPE	140	1.18%
6	5	15"RCP	96	0.52%



NO. DATE: ISSUE DESCRIPTION



IF THIS DOCUMENT IS NOT SIGNED, SEALED, AND DATED, IT MAY NOT BE USED FOR CONSTRUCTION.

RIDGEVIEW BAPTIST CHURCH 3409 TUCKALEECHEE PIKE MARYVILLE, TN 37803

CANNON

10025 Investment Drive, Suite 120 Knoxville, TN 37932

865.670.8555 www.cci-corp.com

CLIENT:

RIDGEVIEW BAPTIST CHURCH 4234 GAMBLE LANE WALLAND, TN 37886 PASTOR WAYNE SEXTON

 CCI PROJ. NO.
 01851-0000.000

 DATE:
 JULY 23, 2025

 PM/PC:
 BCW

 DRAWN BY:
 RHE

SITE GRADING & DRAINAGE PLAN


C201


811

Know what's below Call before you dig


NOTES:


1. REFER TO SHEET CO02 FOR GENERAL NOTES.






CCI PROJ. NO.	01851-0000.000
DATE:	JULY 23, 2025
PM/PC:	BCW
DRAWN BY:	RHE









IF THIS DOCUMENT IS NOT SIGNED, SEALED, AND DATED, IT MAY NOT BE USED FOR CONSTRUCTION.

RIDGEVIEW BAPTIST CHURCH
3409 TUCKALEECHEE PIKE
MARYVILLE, TN 37803

ROJECT:



10025 Investment Drive, Suite 120 Knoxville, TN 37932

865.670.8555 www.cci-corp.com

CLIENT

RIDGEVIEW BAPTIST CHURCH 4234 GAMBLE LANE WALLAND, TN 37886 PASTOR WAYNE SEXTON

CCI PROJ. NO.	01851-0000.000	
DATE:	JULY 23, 2025	
PM/PC:	BCW	
DRAWN BY:	PHE	

SITE DETAILS

C402

